



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण
(पोत परिवहन मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Shipping, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता-७०० ०४३ (प० बं०)
REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

iwaical@yahoo.com
Email : dirkol.iwai@nic.in

IWAI/KOL/Hemnagar/2020-21

Date:-24.03.2021

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Miscellaneous civil works at Hemnagar LC station" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed at, Hemnagar LC station within 4(Four) days from the date of issue work order.
3. 90% payment will be made by cheque/RTGS within 15 days from the date of completion of the work and certification of the bill by the officer concerned after deduction of the statutory dues if any and GST as applicable shall be reimbursed after submission of proof its remittance. Further, balance amount of 10% shall be released after defect liability period i.e 6 month on satisfactory completion of the guaranty period and duly certification by concern officer.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 5% will be charged.
5. The firm should also require submitting self certified copy of PAN Card, Registration certificate, GST, and credential certificate etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 27.03.2021 at 1100 hrs. The sealed bids will be opened on same at 1130 hrs.

DIRECTOR

Head Office : A-13, Sector-I, NOIDA, U.P. Pin - 201301

Phone : 0120-2543972 / 4004 / 2521764, Fax : 0120-02543973 / 4009 / 4041 / 2521664

E-mail : iwainoi@hub.nic.in Website : www.iwai.nic.in / www.iwai.gov.in

BOQ for Miscellaneous civil works at Hemnagar LC station.

Sl. No.	Description of item	Unit	Quantity	Rate (In Rs.)	Amount (In Rs.)
1	Clearing/cleaning of choked septic tank/drain manual/machinery, disposal of waste/garbage pulled out from septic tank/drain at appropriate place and disinfecting the premises with appropriate chemical/materials all complete as per requirement instruction of EIC.	job	1.00		
2	Supplying, fitting and fixing damaged PVC rain water disposal pipe of 150mm dia with all its component clamps, fastener, rivets, collar etc all complete as per specification and direction of EIC	R-m	30.00		
3	Surface dressing & clearance of jungle including removing vegetation and disposal of all rubbish material from site all complete as per specification and direction of EIC	sqm	620.00		
4	Providing and laying in position M20 grade (1:1.5:3) of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work above plinth level in Super Structure all complete as per specification and direction of E.I.C	cum	7.20		
5	Supplying, binding, bending, cutting and laying TMT bars Fe 600 in RCC upto roof level all complete as per specification and direction of EIC	kg	282.60		
6	Centering and shuttering including strutting, propping etc. and removal of form for mass of concrete all complete as per specification and direction of EIC	sqm	32.8		
				Sub total	
				Add remote location charges	
				Grand Total	

Director