



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

File no.-IWAI/KOL/MM/76/22-23/Pontoon

Dated: 27.05.2023

Notice Inviting Quotation

Sealed quotations are invited from reputed and experienced reputed industrial repairer/contractors for construction of 2 nos. mooring pins at Haldia terminals jetty no. 3 as per the 'Annex- I' enclosed herewith on the following term and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, materials etc as per Annexure. No other extra charges will be entertained. GST extra as applicable.
2. The work to be completed within 10 (Ten) days from the date of work order.
3. In case of delay in completion of repair, liquidated damage @0.5% per week days subject to a maximum of 10% will be charged.
4. The firm should submit self certified copy of PAN Card, GST registration, registration certificate, Copy of work experience certificate etc. related to vessel repair/jetty terminal work etc.
5. Payment will be made by cheque or RTGS within fifteen days from date of received of the bills and duly certification by the officer concerned after deducting the statutory dues if any.

The sealed quotation should reach to IWAI, Kolkata Office latest by 31.05.2023 at 1500 hrs. The sealed bids will be opened on 31.05.2023 at 1530 hrs.

Encl: as stated.


Director

Annex-1**B.O.Q for Mooring Pin at Haldia terminals Jetty no 03****Detail estimate for Mooring Pin**

Sl. No.	Description of item	Unit	Quantity	Rate (In Rs.)	Amount (In Rs)	Remarks
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge.	cum	3.38			
2	Brick soling with one brick-on-edge soling including preparation of bed as necessary with brick joints properly filled in and packed with powdered earth and including necessary cushion of similar material below the soling all complete as per direction of E.I.C.	sqm	2.25			
3	Providing and laying Cement concrete M15(1:2:4) as per direction of E.I.C.	cum	3.38			
4	Providing & laying 50mm dia GI wire all complete as per direction of EIC	r-m	13.50			
5	Providing and laying ISMB 200 in the bottom of concrete all complete (1.5 x 25.4 kg/m)	kg	38.10			
6	Providing & laying D-Shackle for tying GI wire at bottom in ISMB 200 and properly aligned and placing the pontoon as required as per direction of EIC	nos	8.00			
Total						

- GST Extra (as applicable)

(Duly authorized to sign the NIQ on behalf of contractor)

Name: