



Phone : 0361-2676925, 2676929, 2570099
Email : dirguw.iwai@nic.in
Website : www.iwai.nic.in

भारत सरकार
GOVT. OF INDIA
पत्तन, पोत परिवहन और जलमार्ग मंत्रालय
Ministry of Ports, Shipping & Waterways
भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण
INLAND WATERWAYS AUTHORITY OF INDIA
Pandu Port Complex, Pandu, Guwahati-781 012, Assam

No. IWAI/GHY/3(13)/Misc/2024/1142

Date: 25.11.2024

NOTICE INVITING QUOTATION

Sealed quotations are invited from the reputed Contractor / agencies for "Providing MS Grill fencing & gate for protecting Green area adjacent to the North side (Right) of the IWAI Office building" as per Annexure as per terms and conditions laid down below. The NIQ can also be downloaded from IWAI's website (www.iwai.nic.in).

- (2) The construction works may be done as per following terms and conditions mentioned below:
- (i) The price may be quoted in both words and figures.
 - (ii) The price may be quoted including all the cost such as supply & installation charges, POL, maintenance, incidental charges and all taxes excluding Good & Service Tax (GST) as applicable which will be paid on production of proof of payment. No other charges shall be entertained.
 - (iii) The above construction work should be as per the BOQ & directives of Engineer-In-Charge or his authorized representative. In case of the supplied items / materials and installation is found in improper condition the supplier should replace the same within one at his own mobilization / de-mobilization cost.
 - (iv) The construction works should be completed within 10 (ten) days from the date of the issue of work order. The other ancillary works are to be carried out as per direction of EIC or his authorized representative.
 - (v) EIC or his authorized representative reserves the right to alter the duration of the work / reduce the quantity of the work as per actual requirement & as per site condition.
 - (vi) The firm has to submit documentary evidence of current copy of the Registration Certificate, PAN and GST.
 - (vii) The payment shall be made by RTGS / PFMS within 30 (thirty) days after satisfactorily completion of work after necessary certification by EIC or his authorized representative. The period of construction will be made as per BoQ on submission of bill as per actual work done and satisfactorily completion, certification by EIC or his authorized representatives.

l

Contd...

Head Office :- I.W.A.I., A-13, Sector-1, NOIDA - 201 301 (U.P.)

● E-mail : iwainoi@nic.in ● Phone No :- 0120-2543972, 2543973, 2544004, 2521664, 2544036, 2522971.

- (viii) In Case of delay in completion of work liquidity damage @ 1.5 % per month to be computed on per day basis. The total amount of compensation for delay to be paid under this condition shall not exceed 5% of the value of work.
- (ix) Necessary compensation in case of any accident will have to be paid by the supplier as per rule and it solely responsibility of the agency to take all necessary / applicable insurance policy etc. IWAI will not be held responsible for any such unforeseen events and no compensation shall be paid by IWAI.
- (x) IWAI reserves the right to accept or cancel any / all quotations without assigning any reason or any prior notice.
- (3) The sealed quotation should reach this office latest by 02.12.2024 at **15:00 hrs** and will open on same day at **15.30 hrs**. No quotation will be accepted after the last date and time for submission of quotations.

Encl: as stated above.



DIRECTOR (I/C)

Copy to: Office Notice Board

BoQ for Providing MS Grill fencing & Gate for protecting Green area adjacent to the North side (Right) of the IWAI Office building					
SI No	Description of items of work	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<p>Supplying, cutting, fabricating, welding, installing of 3mm thickness of MS Square section pipe (50mm x 50mm) (per m weight 4.33 kgs) & (25 mm x 25 mm) (per m weight 2.12 kgs)</p> <p>Total length for fencing = 43m</p> <p><u>For (50mm x 50mm) MS square section (for vertical post)</u> c/c distance = 3000mm or 3 m Total weight including wastage = 126.588 kg----(i)</p> <p><u>For (25mm x 25mm) MS square section (For vertical and horizontal square bars)</u> c/c distance between the = 125 mm or 0.125m Total weight including wastage = 1277.793 kg----(ii)</p> <p>Total Quantity = (i)+(ii) = (126.588+1018.71)Kg = 1404.39Kg</p>	kg	1404.39		
2	<p>Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture (Make: 1st quality of Asian/ Berger) (Grill painting both sides)</p>	sqm	71.38		
3	<p>Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :</p> <p>Ratio : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) for 50mm x 50mm MS square section</p> <p>PCC Below MS square section. Ratio : 1:2:4 (M15)</p>	cum	0.192		
				Total excluding GST Rs.	
In words:					

Note:- All works shall be completed as per direction of EIC or his representative

RWB
Director (I/c)