भाअभजप्रा
iwai
भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण
(पोत परिवहन मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Shipping, Govt. of India)
क्षेत्रीय कार्यालय : पी–७८, गार्डेनरीच रोड, कोलकाता–७०० ०४३ (प० बंo)
REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)
दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570
SAGARMALA
PORT-LED PROSPERITY
Email : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/MM/108/2020-21/CSD Shipra 19.02.2021

Notice Inviting Quotation

Sealed quotations are invited from reputed and experienced ship repairer/builder for painting of CSD Shipra at Ghasuridandga, Ch.367.50, West Bengal as per the annexure enclosed herewith on the following term and conditions.

1.) The price may be quoted including all the costs such as labor, materials and transportation etc. as per annexure. No other extra charges will be entertained. GST shall be reimbursed on submission of remittance.

2.) The work/paint shall be completed at Ghasuridandga, Ch.367.50, West Bengal, within 15 (Fifteen) days from the date/receipt of the work order as per direction of EIC.

3.) The firm should also require submitting self-certified copy of PAN Card, GST registration certificate and work experience certificate etc.

4.) 90% of payment will be made by RTGS within fifteen days from date of receipt of the bill along with receipt challan and duly certification of the bill by the officer concerned after deducting the statutory dues if any. Rest 10 % of amount will be released after expiry of guarantee period.

5.) The work/paint shall be under guaranteed period of six months from the date of completion.

6.) In case of delay in completion of work, liquidated damage @1% per week subject to a maximum of 5% will be charged.

The sealed quotation should reach to IWAI, Kolkata Office latest by 25.02.2021 at 1500 hrs. The sealed bids will be opened on 25.02.2021 at 1530 hrs.

Encl.: As stated.

DIRECTOR

Annexure – B.O.Q.

PAINTING AND CHIPPING etc. of CSD Shipra.

Dimension – (42.67 x 9.486 x 2.284) Meter

SI.No.	DESCRIPTION OF WORKS.	Qty.	Rate (Rs.)	Amount (Rs.)
1.	The entire ship from LWL to main deck, deck plate, superstructure, bathroom, side plate, galley inside, anchor, anchor rake, engine room, store rooms, hydraulic cooling pump room, spud, spud bracket, carriage, vent, cutter ladder, bollard, deck crane, railing with chain, stair with railing, mast light structure, wheel house, draft mark, plimsoll mark and outside along with other fitment etc, are to be proper cleaned, scrapped, wire brushed, chipped and painted by 3 coats of existing colour marine paint. (1 coat zinc chromate primer, followed by two coat of existing colour of marine paints). All pipe lines should be colored as per marine color code. After it name of vessel, deptt. and logo to be made by fluorescent sticker as required as per direction of EIC/ Surveyor.	1200		
				GST extra as applicable.