



# भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

## INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



**SAGARMALA**  
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com  
dirkol.iwai@nic.in

IWAI/KOL/8/TERMINAL/KOLAGHAT/2023-24

Date:-24-01-2024

### NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Providing & laying Precast RCC pillars with concertina wire for barricading the open area of existing land at Kolaghat terminal of IWAI" as per the annexure enclosed herewith on the following terms and conditions.

### TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed at, IWAI terminal at Kolaghat within 7(days) days from the date of receipt of the work order.
3. Payment shall be released by RTGS/online on submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any.
4. In case of delay in completion of works, liquidated damage @1.5% per month computed on daily basis subject to a maximum of 5% will be charged.
5. The firm should also require submitting self certified copy of PAN Card, Registration certificate, GST, and credential certificate etc.

The sealed quotations should be reached RO, IWAI, Kolkata office latest by 29-01-2024 at 1100 hrs. The sealed bids will be opened on same day at 1130 hrs.

-sd-

**DIRECTOR(i/c)**

**Bill of Quantity (BoQ) for Providing & laying Precast RCC pillars with concertina wire for barricading the open area of existing land at Kolaghat terminal of IWAI.**

S No.	Description of item	Unit	Qty	Rate (in Rs.)	Amt. (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (not exceeding 1.5 m in width or 10 sqm on plan ) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-In-Charge	cum	3.67		
2	Supplying at Site: RCC standards post of mixing 1:1.5:3 ( 1 cement, 1:5 coarse sand (Zone-III), 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs of 6mm bar nibs wherever required as per direction of EIC	cum	0.80		
3	Labour Charges of laying of RCC precast pillars all complete as per specification & direction of EIC.	nos	17.00		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level 1:1.5:3 ( 1 cement, 1:5 coarse sand (Zone-III), 3 graded stone aggregate 20mm nominal size all completed as per specification & direction of EIC.	cum	3.66		
5	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length, having 50 nos rounds per 6 metre length, for barricading all complete as per specification & direction of EIC	r-m	167.00		
<b>Total excluding GST</b>					