




भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण
INLAND WATERWAYS AUTHORITY OF INDIA
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)



क्षेत्रीय कार्यालय:

गायघाट, पोस्ट-गुलजारबाग, पटना- 800007

फोन : 0612-2310026

फैक्स : 0612-2310029

(Ministry of Ports, Shipping and Waterways, Govt. of India) Regional Office:

Gaighat, P. O. – Gulzarbagh,
Patna – 800007

Phone/Tele fax : 0612-2310026/29

E-mail: iwaipn@rediffmail.co

No. IWAI/PTN/17(01)/Office Building/2023-24/1565

Date: 02.02.2024

NOTICE INVITING QUOTATION

To

.....
.....
.....

Sub: NIQ for work of Constructing of Ramp at Entrance gate of IWAI RO Patna office- reg.

Inland Waterways Authority of India (IWAI) invites sealed quotation from reputed & eligible contractors for the work of constructing of ramp at Entrance gate of IWAI RO Patna office. Details of work are enclosed as Annex – 1. The terms and conditions are as below:

1. The firm should have experience to execute similar nature of work i.e. civil work, civil maintenance and repair work and office/ institute building repair work etc in last 7 year for costing not less than estimated i.e. 1.34 lakhs. The firm should submit self-certified copy of work completion certificate.
2. The quoted price shall be including all cost, materials, labour, taxes, levies, cess, GST as applicable etc. No other extra charges will be entertained.
3. The firm should submit self-certified copy of firm registration, PAN Card, GST registration and cancelled cheque along with the quotation.
4. Work shall be under guarantee period of Six months.
5. 10% SD will be deducted from the bill and the same will be released after warrenty period i.e. six months from date of completion of the work.
6. 90% Payment will be made through e- mode after completion of work and duly certification of the bill by IWAI concerned officer after deduction of the statutory dues if any.
7. The work shall be completed within 30 days from the receipt of the work order, failing which 0.5% per week L.D. will be imposed.
8. IWAI reserves the right to accept or cancel any quotation without assigning any reason or any prior notice.

The duly filled sealed quotation should reach to this office latest by 12.02.2024 upto 15:00 hrs. The received quotation will be opened on 12.02.2024 at 15:30 hrs.

Encl: As above

Yours faithfully,

For Director

Copy to: IWAI, Patna Notice Board

Bill of Quantities (BOQ)**Name of work: Construction of ramp at Entrance Gate of RO Patna office for Disabled Person**

S. No.	Description of work	Unit/No.	Qty	Rate (Rs.)	Amount (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5m, as directed by Engineer-in charge.	cum	3.35		
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	cum	5.28		
3	PCC work in foundation of half brick masonry work as per specification mentioned in S.No.6	cum	0.15		
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth.	sqm	4.07		
5	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks: 1:4 (1 cement : 4 coarse sand)	sqm	13.56		
6	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Concrete of M20 grade with minimum cement content of 270 kg /cum	cum	1.08		
7	Precast terrazo/terracotta tiles 22 mm thick with graded marble chips of size upto 12 mm, laid in floors, and landings, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete, on 20 mm thick bed of cement mortar 1:4 (1 cement:4 coarse sand) : Ordinary cement without any pigment as directed by Engineer in charge	sqm	17.63		
8	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer, G.I. Pipes	kg	344		
				Total	
				GST as applicable @18%	
				Total including GST	