REPLY ON PRE- APPLICATION QUERIES OF M/S ADANI

SI. No.	Queries	Information
1	Kindly share latest bathymetry charts	The requisite data already been shared with officials of M/s Adani (Mr. Kuldeep Ahulwalia) on 14.09.2022.
2	Kindly share tidal range for the stretches, also share the Locations of installed ATGs and collected data	 Tidal range for NW-5 Krushnadaspur to Dhamara -Paradip i.e. 85 KM from Dhamara Port towards Pankapal (varies from to 2 m to 0.9m) Tidal Range for NW-64 From Paradip upto 43KM towards Upstream (varies from 2.5m to 0.5m) ATG is not available in this office. Tidal gauge readings are taken during MLTS survey and available in the monthly survey report which have already been shared.
3	WAPCOS and FEEDBACK reports have volume projections for Pankapal and not for Padanipal. Please provide cargo projections for Padanipal	At Padanipal no cargo is available. It is an Intermediate Terminal has been proposed between Pankapal and Paradip / Dhamra up to where tidal water available in NW-5.
4	There is no railway connectivity at Padanipal. Nearest railway station is Kendrapara station 54 kms away. Please confirm if this station needs to be considered or only transport from Padanipal to Kalinganagar through road.	The railway station at Kendrapara is to be considered as nearest railway station at 44.00KM from Padanipal. From Pankapal to Padanipal the route is 114.00 KM long by road via Kendrapara. The bidder may advise the economic model.
5	Contract shall mention capital or maintenance dredging	Maintenance dredging.
6	Soil data is not available. Kindly share soil data.	Soil Data near to proposed structures / bridges received from SM Consultants and Tractebel Engineering Pvt. Limited can be shared.

7	What are the exact coordinates for proposed terminal locations at Padanipal, Marshaghai, Dhamra and Paradip	 The Proposed terminal at Pankapal & Talcher as identified on the village map may be shared. For terminals at Padanipal, marsaghai, Dhamara and Paradip no land has been identified. However, the agency is advised to opt as per the requirement.
8	The stretch of NW-64 Paradip to Marshaghai, no volume projections are indicated. Only 0.62 MMTPA from Paradip to Cuttack is indicated in FEEDBACK report. These volumes are very low. Please confirm Marshaghai Terminal requirement w.r.t cargo projections	The terminal at Marsaghai can reduce the congestion of traffic at Paradip Port. The ODC movement for Industries at Kalinganagar can be considered from Marsaghai terminal for movement from sea to river to road movement.
9	Has IWAI checked the maximum capacity utilization of railway from Dhamra / Paradip to Kalinganagar(including enhancement on account of python trains and automated signaling)	No.
10	What would be the MGT for the volume projection of 11.75 MMTPA (FEEDBACK report 2016 for NW-5)	Traffic study by the Consultant being engaged is under progress
11	Instead of DBFOT, is EPC option available as the CAPEX is very high with limited to recovery options.	The project to be taken through PPP model for select stretches of Phase-I.
12	Proposed or identified locations on the stretches which required land filling for the purpose of land protection, where dredged material shall be disposed.	Govt.Land will be identified at the time of dredging.

13	Please share following information for Talcher to Paradeep & Dhamra stretch	
13.1	List and details of all road and rail bridges from Talcher to Dhamra/ Paradip	List enclosed as Annexure-1.
13.2	For all the bridges, Kindly share the water draft & air draft level available at the time of: a) Low flow b) High flow c) Flood	Statement enclosed as Annexure-2
13.3	 What is peak discharge criteria during monsoon or heavy flooding for barrages Height and width of navigational locks and barrages 	 Free flow no shutter or any control structure at Tantighai and Jokadia. There is no navigational lock in the weir at Sujanpur and weir cum barrage with Foot Bridge at Jokadia.
13.4	What is the biggest navigable span in the NW- 5	 The width of the navigable river varies between 500 m to 650m in the following reaches of NW-5 : 1. From Dhamara to Padanipal(Kalamada)via Mangalgadi (Chainage 00 to 70 00KM) 2. From Hansua Mouth(Paunsiapal) to Ramchandi Galia(Chainage 17.00KM to 32.00KMconsidering 0.00 at Mangalgadi) 3. From Jokadia to Pankapal (Chainage from 144.00KM to 155.00KM) 4. However, the navigable span at Gadgadighat & Rajnagar bridge is 100 m.

13.5	Any underground pipeline like gas line, liquid line & underground electrical crossing. If yes, please share map and details of the crossings	 Underground JSW slurry pipe line at Pankapal across NW-5 (Chainage 154.900KM) and at Marshaghai across NW-64on the upstream of NH-53 bridge.(Google Maps and C/S enclosed) Gas pipe line of GAIL India across NW-5 at Baringi village(Ch.89.00 from Dhamara) in Jajpur district across river Kani and across river Mahanadi near village Akhadasali in Kendrapara district.(Google Maps and C/S enclosed)
13.6	How many weirs are there in NW-5	 a. Existing weir cum Barrage at village Jokadia with foot bridge (chainage 143.54 KM from Dhamra) b. Existing weir (Defunct) on Tantighai near village Sujanpur at change 114.87 KM from Dhamara After mathematical model study IIT, Gwahati has proposed to construct three Numbers of Barrages with lock gate across river Karashrota& river Tantighai at Jokadia, Kacherigan and Sujanpur(W1,W2,W3) respectively, One rubber dam with barrage and lock gate (W5) at Padanipal, one weir cum barrage at Kamalpur across river Kharashrota (W4), one weir at Jenapur across river Brahmani (W Jn) and two Checkdams at Erada and Udaynathpur(C1&C2).
13.7	What is the height and depth of water upstream of weir	Depth of water upstream of weirs a. Tantighai-3.70M(On 17.09.2022) b. Jokadia- 6.10M(On 15.09.2022)
13.8	How many barrages are there in NW-5	Existing weir cum Barrage at village Jokadia with foot bridge (chainage 143.54 KM from Dhamra)

13.9	How many causeways are there in NW-5	No causeway across waterways (NW-5 and NW-64)
13.10	Commitment of water by State government as we are planning to build barrages and weirs to maintain navigable depth.	An MoU will be signed with Govt. of Odisha. Favorable Commitment as all steps is taken with compliance observations of Water resources Department, Government of Odisha
13.11	Kindly share details of transmission lines and overhead lines along with height and span data during a) Low flow b) High flow c) Flood	Below NH-16 (up to Ch. 130 from Dhmra) all low-level transmission lines have been modified and lifted by the State Government on deposit basis as per the criteria notified by MoPS&W.
13.12	Kindly share the existing railway capacity	Not available with IWAI
13.13	Kindly share the capacity utilization along with the relevant speed parameter considered for its derivation for railways. Capacity utilization for low speed as well as highest speed of train is required	Not available with IWAI
13.14	What is the incremental capacity available for the railways	Not available with IWAI
13.15	Does the railway have land adjacent for expansion (ROW) for line doubling? If yes, kindly share the expandable capacity. This is required to estimate maximum future capacity through railway	No information available with IWAI.
13.16	At every barrage location, can we have a holding pond to have water neutrality	Yes

completion of fairway development in NW-5 between Talcher and Padanipa 3. Traffic study is proposed to be considered by the Consultant deployed b What is maximum CAPEX funding possible if	13.17	 Has any social impact study been carried out What are the existing obligations for local community in terms of drinking, industrial and irrigation water 	Social Impact Study has not taken up
15 project economics requires, Is 100% Govt. VGF funding up to 40% can be considered for development on PPP model	14	 Cargo will take out of Talcher region to Dhamra / Paradeep i.e. connecting the Cargo to Terminals for barge loading at Talcher and then barge transportation uptoDhamra and Paradeep. The cargo potential divertable in route described in point 1 above. Traffic Study for point no. 1 and 2 above to assess the current and future 	 a. Talcher to Jenapur through river Brahmani b. Jenapur to Sujanpur through river Kharshrota c. Sujanpur to Padanipal through river Tantighai& river Kani d. Padanipal to Mangalgadi through river Kharshrota e. Mangalgadi to Dhamara through river Brahmani f. Mangalgadi to Hansua mouth through river Hansua g. Hansua mouth to RamachandiGalia through Hukitola Bay h. RamachandiGalia to Musadia through Kharinasi Creek i. Musadia to Mahanadi mouth through Mahanadi j. Mahanadi Mouth to Paradip port through Bay of Bengal 2. The cargo potential may be diverted in route described in point 1 above till completion of fairway development in NW-5 between Talcher and Padanipal 3. Traffic study is proposed to be considered by the Consultant deployed by
		project economics requires, Is 100% Govt.	VGF funding up to 40 % can be considered for development on PPP model.
16If project economics requires, is 99 year lease possible?Bidder may provide the detailed breakup for obtaining the approval from th MoPS&W.	16		Bidder may provide the detailed breakup for obtaining the approval from the MoPS&W.

SI.	Name of Structure	Location	Authority	Present
No.		LOCATION	Authonity	condition
	NW-5 (Phase-I)			
1	Railway bridge-I	Jenapur	Indian Railways	Existing
2	Railway bridge-III	Jenapur	Indian Railways	Existing
3	Railway bridge-III	Jenapur	Indian Railways	Existing
4	Jokadia Anicut	Jokadia	WR	Existing
5	HL Bridge at Jokadia	Jokadia	Works	Existing
6	Major Bridge at Sahapur-I	Sahapur	NHAI	Existing
7	Major Bridge at Sahapur-II	Sahapur	NHAI	Existing
8	Major Bridge(2 Lane) at Km 82.885 (Sahapur) Sahapur-III	Sahapur	NHAI	NOC issued To be constructed
9	HL Bridge at Jahal ghat	Jahal	Works	Existing
10	HL Bridge at Badabanta	Badabanta	NH(Odisha)	Existing
11	HL Bridge at Sujanpur	Sujanpur	WR	Existing
12	H.L.Bridge over river Tantighai at 3rd km on MDR-14 to Kantia via Bhanra-Bhurunga road in the district of Jajpur	Bhurunga	RW	NOC issued To be constructed
13	HL bridge over river Chingudia nalah near Ratlang	Ratlang	RW	NOC issued Under construction
14	H.L.Bridge over river Pandua on Kalamatia- Binjharpur road	Kalamatia-Binjharpur road	Works	NOC issued Under construction
15	HL bridge over river Kanthia Nalah near Krushnadaspur	Krushnadaspur	RW	NOC issued Under construction
16	HL Bridge at Manpur	Manpur	RW	Existing
17	HL Bridge at Gadgadighat	Gadgadighat	Works	Existing
18	H.L.Bridge over river Kharashrota on Nuabazar-Balituraghat road(NW-5)	Nuabazar-Balituraghat road	RW	To be constructed
19	H.L.Bridge over river Kani at Kalamada on RD road to Padanipal road(NW-5)	RD road to Padanipal road	RW	To be constructed
20	HL Bridge at Rajnagar over River Hansua	Rajnagar	Works	Existing
21	Jaynagar bridge over Brahmani	Jaynagar	NH(Odisha)	NOC Applied To be constructed
22	HL bridge over river Matai at 8 km on Kerasahi-Baliapal ghat Road to Balimed road	Kerasahi-Baliapal ghat Road to Balimed road	Works	NoC Issued To be constructed
23	HL bridge over river Matai on PWD Road to Balimed road	PWD Road to Balimed road	Works	NoC Issued To be constructed
24	HL bridge over river mantei at 10th km on	Dogachhia-Bansada road	Works	Under

construction

Dogachhia-Bansada road

NW-5 (Phase-II)

25	Railway bridge at Samal	Samal	Indian Railways	Under construction
26	Major Bridge at Talcher on Brahmani	Talcher,	NHAI	Existing
27	Major Bridge at Talcher on Brahmani	Talcher,	NHAI	NOC issued Under construction
28	Rail bridge at Kamalanga	Kamalanga	Indian Railways	Existing
29	H.L.Bridge at Khadagprasad on Brahmani	Khadag Prasad	R&B	NOC issued Under construction
30	H.L.Bridge at Bridge at Gengutia	Gengutia/ Kamagara	R&B	Existing
31	H.L.Bridge over river Brahmani on Goradia- Kaluria ghat road in the District of Dhenkanal	Kaluria	R&B	NOC issued Under construction
32	H.L.Bridge at Bridge at Mandara	Mandara	RW	Existing
33	H.L.Bridge at Bridge at Bahabalpur	Bahabalpur	RW	Existing
34	Major Bridge at Ch 10+407 on the Brahmani Bridge(Pankapal)	Pankapal	NHAI	NoC Issued To be constructed
35	Existing NHAI bridge at Pankpal	Pankapal	NHAI	Existing
	NW-5 (Phase-III)Odsha Coast canal			
36	H.L.Bridge over coast canal at 2nd KM on Kulhachhad to Badatalapada road in the Dist. of Balasore	Kulhachhad to Badatalapada road	RW	NOC issued Under construction
37	H.L.Bridge over coast canal at 4th KM on Jaleswarpur to Batagram road in the Dist. of Balasore	Jaleswarpur to Batagram road	RW	NOC issued Under construction
	NB-There are number of bridges across Odsha Coast canal which are not traced out and no more information avalable in this office			

Annex-2

	Vertical clearance of existing bridges from Dhamra to Pankpal as per NHFL calculation by SM Consultant																
Gagadighat Manpur Sujanpur Badabanta Jahalghat											Sahapur-1						
HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc
4.027	3.762	4.958	6.41	6.145	1.43	13.469	13.204	2.171	14.576	14.311	2.309	16.794	16.529	1.371	17.256	16.991	4.618
	Vertical clearance of existing bridges from Mangalgadi to Paradip as per NHFL calculation by SM Consultant																
	Rajnagar Sahapur-2 Jokadia																
HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc	HFL	NHFL	Vertical Clearanc									
2.191	2.191	4.764	17.256	16.991	4.618	20.54	20.275	1.315									

Month	Gagadighat	Manpur	Sujanpur	Badabanta	Jahalghat	NHAI Sahapur-1	Sahapur-2	Jokadia	Railway bridge -1	Railway bridge -2	Railway bridge -3	Pankpal	Rajnagar
June, 2020	7.50	8.20	7.60	5.80	4.80	6.90	8.00	4.90	5.90	10.30	7.10	8.80	6.00
July, 2020	7.50	8.20	7.60	5.80	4.80	6.90	8.00	4.90	5.90	10.30	7.10	8.80	6.00
Aug., 2022	4.00	4.80	4.80	3.10	1.30	4.90	5.90	2.00	4.20	8.00	6.30	9.30	6.00
Sept., 2020	5.40	5.20	6.60	5.70	3.30	6.40	6.70	5.30	5.50	9.10	7.10	10.10	3.30
Oct, 2020	4.70	3.90	8.00	7.00	5.00	8.80	6.70	5.40	7.10	11.50	7.80	9.30	4.70
Nov., 2020	5.90	4.70	8.10	3.90	4.10	7.90	8.70	6.10	8.80	11.80	8.40	10.90	6.90

Vertical clearance(Air draft) of existing bridges from Dhamra to Pankpal as per MLTS report conducted by GMI

Water draft of existing bridges from Dhamra to Pankpal as per MLTS report conducted by GMI
--

Months	Gagadighat	Manpur	Sujanpur	Badabanta	Jahalghat	Sahapur-1	Sahapur-2	Jokadia	Railway bridge -1	Railway bridge -2	Railway bridge -3	Pankpal	Rajnagar
June, 2020	7.80	4.00	3.40	3.60	3.40	3.70	3.10	3.50	1.50	1.80	1.00	2.80	2.80
July, 2020	5.62	6.28	4.40	3.70	4.00	2.10	3.90	2.20	1.60	2.00	2.50	2.60	10.71
Aug., 2022	7.80	5.80	6.30	5.40	7.00	6.20	5.30	6.30	5.30	4.60	2.80	2.30	11.00
Sept., 2020	6.40	5.40	4.50	2.80	5.00	4.70	4.50	3.00	4.00	3.50	2.00	1.50	11.60
Oct., 2020	7.00	6.70	3.10	1.50	5.00	4.50	2.90	2.40	2.40	1.10	1.30	2.70	10.00
Nov., 2020	5.90	5.90	3.00	4.60	4.20	3.20	2.50	2.20	0.70	0.80	0.70	0.70	8.00

Horizontal clearance of existing bridges from Dhamra to Pankpal as per MLTS report conducted by GMI(Phase-I)

6. 0.	Locations	Horizontal Clearance (In m)
1	Gagadighat	100.00
2	Manpur	24.00
3	Sujanpur	30.00
4	Badabanta	20.00
5	Jahalghat	24.00
6	Sahapur-1	30.00
7	Sahapur-2	34.00
8	Jokadia	36.00
9	Jokadia/Anicut/weir/Barrage	8.00
10	Railway bridge-1	41.00
11	Railway bridge-2	45.00
12	Railway bridge-3	43.50
13	Pankapal bridge	30.00

conducted by GMI

Rajnagar

14

92.00

