



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)
REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/MM/76/PONTOON/2022-23

20th July 2024

NOTICE INVITING QUOTATION

Sealed quotations are invited from the reputed Contractor/repairer/authorized dealer for Renewal of underwater, deck and side plate of Modular Pontoon at Haldia Pati Khali as per annexure & terms and conditions laid down below. The NIQ can also be downloaded from IWAI's website (www.iwai.nic.in).

- (2) The supply work may be done as per following terms and conditions mentioned below:
- The price may be quoted in both percentage and figure.
 - The price may be quoted including all the cost such as labour, transportation charges, and loading-unloading etc. **No other charges shall be entertained.** GST extra as applicable.
 - The repair work must be completed within 25 days from the date of receipt of order from R.O. Kolkata.
 - The firm has to submit documentary evidence of current copy of the Registration Certificate, PAN, GST and Experience with similar work.
 - The payment shall be made by RTGS/ PFMS within 15 days from the date of receipt of bill and challan after satisfactorily work done. The copy of RTGS details shall be submitted along with quotation.
 - 90% payment will be release on completion of work. Remaining 10% will be release after completion of Guarantee period.
 - In Case of delay in completion of work liquidity damage @ 1% per week subject to a maximum of 10% will be charged.
 - IWAI reserves the right to accept or cancel any / all quotations without assigning any reason or any prior notice.
- (3) The sealed quotation should reach this office latest by **25-07-2024** at **15:00 hrs.** and will be open on same day at **15:30 hrs.** No quotation will be accepted after the last date and time for submission of quotations.

Encl: as stated above.

श्रीमज्जा
DIRECTOR

- Copy to: -
1. Notice Board, IWAI Kolkata.
 2. Notice Board, SMPK.
 3. IWT Directorate, Govt. of West Bengal.

BOQ for repair of 1 no. Modular Pontoon at Haldia Pati Khali site

#	DESCRIPTION OF WORK	Unit	QTY	Rate (Rs.)	Amount (Rs.)
1	Cropping & renewal of underwater plate, deck plate, side plate of 8 mm thickness & other inside/outside fitments after ultrasonic testing to renew the plate, as per report of Ultrasonic test as directed by EIC/IWT surveyor.	Ton	2	1,32,048.00	2,64,096.00
2	Painting of underwater hull plate & deck to be done by three coats (1 coat zinc primer and 2 coat finish paint) as painting scheme after proper chipping, wire brushing and cleaning as required as per direction of EIC	Comp. Job	1	20,000.00	20,000.00
3	Ultrasonic testing to be made hull, deck plate and hull to LWL Ship side Port 7 stbd for thickness as per direction of EIC	SPOT	50	60.00	3,000.00
4	Lifting, blocking of modular pontoon at Haldia as per the direction of EIC	No	1	10,000.00	10,000.00
Total estimated cost					2,97,096.00
Quoted Price in (+/-) Percentage (%)					
Quoted Price in (+/-) Amount					

*GST Extra as applicable

