



# भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

**INLAND WATERWAYS AUTHORITY OF INDIA**  
(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)  
REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)  
दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



E-mail : iwaical@yahoo.com  
dirkol.iwai@nic.in

**IWAI/KOL/8/BTPS Jetty/2023-24**

**Date:-14-09-2023**

## **NOTICE FOR INVITING QUOTATION**

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of 3 nos of mooring pins & replacement of wooden plank of walkway at BTPS jetty, Tribeni" as per the annexure enclosed herewith on the following terms and conditions.

### **TERMS & CONDITIONS**

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST which shall be reimbursed only after submission of proof of its remittance.
2. The work shall be completed at, BTPS jetty, Tribeni within 15(Fifteen) days from the date of receipt of the work order as per direction of E.I.C and his representative.
3. 90% payment shall be released by RTGS within 15 days from the date of submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% will be released after completion of guarantee obligation period of 6 month on duly certification of the officer concerned.
4. In case of delay in completion of works, liquidated damage @1.5% per month computed on daily basis subject to a maximum of 10% will be charged.
5. The firm should also require submitting self certified copy of PAN Card, Registration certificate, GST, and credential certificate etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 20-09-2023 at 1100 hrs. The sealed bids will be opened on same at 1130 hrs.

**DIRECTOR(i/c)**

**BoQ for Construction of 3 nos of mooring pin & replacement of wooden plank of walkway at BTPS, jetty, Tribeni**

Sl. No.	Description of item	Unit	Qty.	Rate (In Rs.)	Amount (In Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge.	cum	6.75		
2	Providing and laying Cement concrete M15(1:2:4) as per direction of E.I.C.	cum	6.75		
3	Supplying of 4 m length ISMB 200 all complete (4 x 25.4 kg/m)	kg	304.80		
4	Labour for driving Joist 2m below GL (i.e after eartwork in f/t upto 1.m only 2 m is to be driven) and 1m above G.L all complete as per specification & direction of EIC	r-m	6.00		
5	Supplying, fabricating & fixing wooden plank of Second class teak wood in sleeper in walkway at jetty all complete Total 10 nos of sleeper is reuired	cum	0.80		
Total					