



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फेक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/8/Terminal/Kolaghat/2022-23

17/01/2023

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from experienced, bonafide and resourceful contractors for the work "Construction of Temporary Bank Protection Works for a length of 9.0 m for retaining earth at IWAI's Kolaghat IWT Jetty, River Rupnarayan, NW-86, District: Purba Medinipur, West Bengal" as per the General Terms & Conditions given below. The details of the work and B.O.Q are enclosed as "Annexure - A" with this NIQ, which is to be filled up and submitted. Drawing enclosed as "Annexure - B"

The details of the works are as under:-

1. Name of Work "Construction of Temporary Bank Protection Works for a length of 9.0 m for retaining earth at IWAI's Kolaghat IWT Jetty, River Rupnarayan, NW-86, District: Purba Medinipur, West Bengal"
2. Last date for submission of quotation: 23.01.2023 upto 1300 hours
3. Date of opening of the quotation: 23.01.2023 at 1330 hours
4. Venue for 2 & 3 is O/o the Director's Office, IWAI Kolkata, R.O.

For further details please contact IWAI office or visit website at www.iwai.nic.in

General Terms and Conditions

1. The firm must have at least two years experience of works in carrying out bank protection/construction of temporary retaining structures in rivers/canals/on shore.
2. The firm shall be registered in appropriate class with CPWD, Railways, MES, State PWD/ Irrigation Department, Port Trust etc. or having experience with IWAI for similar type of work and should submit credential for similar works carried out by them.
3. Bidder shall visit the site prior to quote the rates before submission of quotation for the work.
4. The rates should be quoted inclusive of all taxes, duties, materials, transportation and any other levies etc., excluding Goods & Service Tax (GST). No additional payment on any such account shall be payable by the Employer. However, GST would remain effective as per the Government Guidelines, which shall be paid as per the provisions effective at the time of release of payments. The rates shall be quoted legibly both in figure and words and shall be valid up to 30 (Thirty) days from the date of opening. No extra cost will be admissible.

Contd... P/2

5. IWAI reserves the right to accept or reject any or all quotation(s) without assigning any reason thereof.
6. The firm should also require submitting self certified and stamped copy of PAN Card, GST Registration certificate, Copy of work experience certificate, financial capability and Bank account details etc.
7. Incomplete quotations will be summarily rejected.
8. Any modification in offer after the closing date will not be considered. Quotation, received late, will not be considered. IWAI will not be responsible for any postal delay
9. 90% of the contract value shall be released by online within 15 days on the completion of work as per the scope of the work, BOQ and certification of the bill by the officer concerned after deduction of the statutory dues. Balance amount 10% shall be released after defect liability period 6 (six) months on satisfactory completion of the guaranty period and duly certification by concern officer. Further, GST as applicable shall be reimbursed only after submission of proof of its remittance.
10. The Work shall be completed in 20 (Twenty) days.
11. The Engineer-in-Charge or his representative will inspect, co-ordinate, and certify the work. He has the right to inspect at any time during the contract period for which contractor's authorized agent shall be available at site during such inspection.
12. If the Contractor's personnel or any outside labour employed to work during execution of Contract, breaks or damages / destroys any vessel, craft, net, fishing stakes etc. building, road, kerb, water pipe, fence, bund, wires, trees, crop, fruit or cultivated ground etc., during the period of agreement, the same shall be made good by the Contractor at his own expenses or in default, the Employer may cause the same to be made good by other sources and deduct the expenses from any sums that may be then or at any time thereafter may become due to the contractor.



(Arvind Kumar)
Director I/C

Bill of Quantity for "Construction of Temporary Bank Protection Works for a length of 9.0 m for retaining earth at Kolaghat IWT Jetty, River Rupnarayan, NW-86, District: Purba Medinipur, West Bengal"

Sl. no.	Description of item	Unit	Quantity	Rate excluding GST in (₹)	Amount excluding GST in (₹)
1.01	Earth work in surface excavation: Earth work in surface excavation in all kinds of soil not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	sqm	36.00		
1.02	Compacted bed of course sand in surface excavation: Supplying and filling of course sand in surface excavation including watering, ramming, consolidating and dressing etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	cum	3.60		
1.03	Wooden Toe Wall: Supplying Jhaw / Eucalyptus bullah piles of 17.5 cm av. diameter and 4.8 m length at work site, including dressing and making one end pointed and painted with coal tar epoxy etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	r-m	172.80		
1.04	Labour for driving Jhaw / Eucalyptus bullah piles by monkey in all sorts of soil including hoisting and placing piles in position, protecting the pile head with iron ring and cutting and shaping heads before and after driving and including hire and labour for necessary driving appliances and all tackles etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	r-m	115.20		
1.05	Supplying, fitting and fixing half split Jhaw / Eucalyptus ballahs of 17.5 cm dia Horizontal member for tieing with Ballah piles at work site, including dressing and making and painted with coal tar epoxy etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	r-m	54.00		

1.06	Supplying, fitting and fixing M 24 mm x 400 mm hexagonal nut & bolt with ballah piles & hlaif split horizontal ballah etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	kg	174.96		
1.07	Bitumen drum sheet wall: Supplying, fitting and fixing of bitumen drum sheets to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails @ 20cm c/c at top & bottom and bolts& nuts at top & bottom at every joint of drum sheet with a laping of 15 cm, including supply of drum sheet, fixture etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	sqm	12.83		
1.08	Weepholes: Supplying and palcing of 80 NB GI Pipes of WT 4.05 mm in weepholes etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	r-m	19.00		
109	Sand bags: Supplying and laying in position of HDPE bags filled with not less than 0.0328 cum of locally available yellow sand/siver sand in each bag machine stitched etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	nos	1215.00		
1.10	Nylon Cage: Sypply and caging of sand bags layed in position with Nylon net, knot having mesh size 17.5 cm x 17.5 cm constructed with Nylon thread (210 x 24) having tensile strength not less than 250 kg /sq. cm etc., all complete, as per drawing, Technical specifications and as per direction of Engineer-in-charge.	sqm	116.90		
Total in Figures					

Quoted Rate in Words including all taxes excluding GST:

Note: During Financial Bid Evaluation, for selection of lowest Bidder, quoted cost excluding GST would be considered. However, GST would remain effective as per the Government Guidelines, which shall be paid as per the provisions effective at the time of release of payments.

Authorized Signatory :

Name :

Designation :

Name of Firm :

Address :

Director(I/C)

