



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/8/TERMINAL/2023-24

Date:-30-01-2024

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of Temporary store room near RIS Station BISN GRJ-I" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed near RIS Station BISN GRJ-I within 15 (Fifteen) days from the date of receipt of the work order.
3. 90% payment will be made by RTGS/online on submission of bill after completion of the work and duly certified bill by the officer concerned after deduction of the statutory dues and balance amount of 10% shall be released after defect liability period i.e 6 month on satisfactory completion of the guaranty obligation period and duly certification by concern officer.
4. In case of delay in completion of works, liquidated damage @1.5% per month to be computed on daily basis subject to a maximum of 10% will be charged.
5. The firm should also require submitting self certified copy of PAN Card, Registration certificate, GST, and credential certificate etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 05-02-2024 at 1100 hrs. The sealed bids will be opened on same at 1130 hrs.

-sd-

DIRECTOR(i/c)

Head Office : Jalmarg Bhawan, A-13, Sector-1, NOIDA - 201 301 (U.P.)

Phone : +91-120-2544036, 2543972, 2527667, 2448101, Fax : +91-120-244009, 2544041, 2521764, 2543973

Website : www.iwai.gov.in / www.iwai.nic.in Email : iwainoi@nic.in

Bill of Quantity (BoQ) for Construction of Temporary store room near RIS Station BISN GRJ-I.

S No.	Description of item	Unit	Qty	Rate (In Rs.)	Amt. (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	cum	4.00		
2	Providing & Laying 75A designation brick flat soling all complete as per specification & direction of EIC.	sqm	132.00		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) all complete as per specification & direction of EIC. (In base of f/t)	cum	0.60		
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level in M20 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) all complete as per specification & direction of EIC.	cum	1.01		
5	Providing TMT bars in Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete as per specification & direction of EIC.	kg	79.29		
6	Providing centring & shuttering upto plinth beam all complete as per specification & direction of EIC				
	In column & footing	sqm	3.59		
	In Plinth beam	sqm	5.30		
7	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement all work above plinth beam in M20 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) all complete as per specification & direction of EIC.	cum	1.22		
8	Providing TMT bars in Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete as per specification & direction of EIC.	kg	95.77		

S No.	Description of item	Unit	Qty	Rate (In Rs.)	Amt. (Rs.)
9	Providing centring & shuttering Structure upto in super structure all complete as per specification & direction of EIC				
	In column (above P.L)	cum	13.70		
	In Lintel Beam	cum	3.30		
10	Brick work with clay flyash F.P.S. (non modular) brick of class designation 7.5 in superstructure above plinth level up to floor five level in : Cement mortar 1:4 (1 cement : 4 coarse sand) all complete as per specification & direction of E.I.C	cum	2.48		
11	Providing 12 mm thick cement plaster in CM(1:4) in faced wall (outer side) all complete as per specification & direction of EIC	sqm	30.43		
12	Providing 15 mm thick cement plaster in CM(1:4) in unfaced wall (inner side) all complete as per specification & direction of EIC	sqm	30.69		
13	Supplying, fitting & fixing of 50mm x 50mm ms square pipe with 2.9 mm wall thickness for frame of roof.	kg	153.96		
14	Supplying, fitting & fixing of color coated roof sheet of 0.63mm thicknees in roof all complete as per specification & direction of EIC	sqm	20.95		
15	Supplying, fitting & fixing rain water pipe in the periphery of roof alongwith its discharge pipe all complete as per specification & direction of EIC	r-m	10.60		
16	Supplying and laying brick bats & rabbish in filling of floor all complete as per specification & direction of EIC	cum	7.34		
17	62 mm thick cement concrete flooring with concrete hardener topping, under layer 50 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and top layer 12mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate, 6mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacture's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	sqm	10.80		
18	Finishing walls with textured exterior paint of required shade all complete as per specification & direction EIC	sqm	61.12		

S No.	Description of item	Unit	Qty	Rate (In Rs.)	Amt. (Rs.)
19	Providing and fixing 1mm thick M.S. sheet door in living room with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer Using M.S. angels 40x40x6 mm for diagonal braces all complete as per specification and direction of EIC.	sqm	1.89		
20	Providing MS angle of ISA 40 x 40 x 6 mm frame for ventilator all complete as per specification & director of EIC	kg	8.13		
21	Providing & fixing 5.5mm thick glass panes with putty and glazing clips in ventilators all complete as per specification & direction of EIC	sqm	0.81		
22	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution all complete as per specification & direction of EIC	sqm	3.78		
23	Providing all electrical works i.e 4 points of LED bulbs in each room, electrical wiring of both rooms with wire, switches, sockets, PVC boad, wiring pipe and 2 LED bulb point at entrance with protection steel jali on it all complete as per specification & direction of EIC.	job	1.00		
Total					