



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० बं०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/MM/78/2020-21

Date:- 21.02.2022

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of PCC walkway at RO IWAI, Kolkata premises" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed at, IWAI, Kolkata within 5(Five) days from the date of receipt of the work order.
3. 90% payment shall be released by RTGS within 15 days from the date of submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% shall be released after 6 month on duly certified by officer concerned on satisfactory completion of the guaranty period. Further, GST as applicable shall be reimbursed, only after submission of proof of its remittance from concerned department.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 5% will be charged.
5. The firm should also require submitting self certified copy of PAN Card, Registration certificate, GST, and credential certificate etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 02.03.2022 at 1100 hrs. The sealed bids will be opened on same at 1130 hrs.

-sd-

DIRECTOR

Bill of quantity for construction of PCC walkway at RO IWAI, Kolkata premises

| Sl. No. | Description of item | Unit | Quantity | Rate (In Rs.) | Amount (In Rs.) |
|-----------|--|------|----------|---------------|-----------------|
| 1 | Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of all rubbish material from site and making the level of road throughout constant all complete as per specification and direction of EIC | sqm | 88.00 | | |
| 2 | Providing & laying brick on edge soling all complete as per specification & direction of EIC (54 brick in 1 sqm) | sqm | 4752.00 | | |
| 3 | Providing and laying cement concrete M15(1:2:4) on prepared base of BES all complete as per specification and direction of EIC | cum | 8.80 | | |
| 4 | Centering and shuttering including strutting, propping etc. and removal of form for mass of concrete all complete as per specification and direction of EIC | sqm | 9.2 | | |
| Sub total | | | | | |